

GEV/ADM-ZAM/087/21 25. Mac. 2021

Pengarah Jabatan Perkhidmatan Digital, Universiti Teknologi Malaysia, UTM Johor Bahru, JOHOR

U/P: Tuan Nik Kamal Izuddin B. Nik Ibrahim

Profesor Madya,

SUMBANGAN PENGUBAHSUAIAN HP COMMERCIAL LAB DI BANGUNAN JABATAN PERKHIDMATAN DIGITAL, UTM SKUDAI, JOHOR.

Perkara di atas adalah dirujuk.

- 2. Sukacita dimaklumkan bahawa sebagai Authorised Partner bagi HP Inc., pihak Global Elite Ventures San Bha telah berbesar hati untuk memberi sumbangan kepada Jabatan Perkhidmatan Digital, Universiti Teknologi Malaysia dalam bentuk pengubahsuaian bilik.
- 3. Di antara perkara yang akan dijalankan adalah merangkumi kerja-kerja dan pembekalan di bawah:

Bil.	Perkara	Kuantiti / Unit
1.	CEILING AND PARTITION WORKS	
	1.1 To supply labaour and material to demol	ish and install 695 SF
	plaster ceiling for exisitng t-grid pinhole	
	Material: Gypsum board plaster ceiling	
	1.2 To supply material to paint the entire plast selected color	er ceiling with 695 SF
	1.3 To supply labour and material to install single	e side partition 340 SF
	on existing wall	330 SF
	Material: 12mmTk gypsum board	338 SF
	1.4 To supply labour and material to demolish ex and install new double sided partition wall	sisting partition 330 SF
	Material: 12mmTk gypsum board	
	1.5 To supply labour and material to install new mainhole	access panel 2 UNIT
	Material: Gymsum board mainhole	
	1.6 To supply material to paint the entire wall color	with selected 505 SF
2.	FLOORING WORKS	
	2.1 To supply labour and material to install c	arpet flooring 765 SF
	(Included 10% wastage)	
	Material: Carpet flooring	
	2.2 To supply labour and material to beading for	r door area 8 FR

3.	WIRING & ELECTRICAL WORKS				
J.	3.1 To supply and lay new wiring in PVC conduit:-				
		13A power point	16 NO		
		Lighting point	44 NO		
		Cat6e internat point	1 NO		
		Telephone point	1 NO		
		CCTV network cable point	1 NO		
		Cat5e CCTV cable point (Wiring only)	4 NO		
		Emergency light point	2 NO		
		Exit sign point	2 NO		
	3.2	To supply and install new light fitting w/ using metal rod:-			
		13A power socket	16 NO		
		Ceiling haging light 4ft	3 NO		
		LED downlight	36 NO		
		Emergency light	2 NO		
		Exit sign (Keluar sign)	2 NO		
		DB Box	1 NO		
	3.3	Preparation & submission of require O&M manual and	1 LS		
		single line diagram c/w Borang G, H and testing report			
	3.4	Testing and commissioning	1 NO		
4.		AGE & ADVERTISING WORKS	, , , , ,		
	4.1	To supply and install HP stainless steel box up front lit logo	1 NO		
		Material: Stainless Steel Box Up Front Lit Logo			
	4.2	To supply and install LED lightbox poster	38 SF		
		Material: 78mm aluminium lightbox w/ fabric poster	32 SF		
5.	CARE	PENTRY AND FIT-OUT WORK	02 0.		
٠.	5.1	To supply and install wall wooden panel	88 SF		
		Material: Plywood material c/w wooden laminate finishing	00 0.		
	5.2	To supply and install hp display low cabinet	14 FR		
		Material: Plywood material c/w selected laminate finishing			
		and storage compartment lockable door			
	5.3	To supply and install HP island kiosk	1 NO		
		Material: Plywood material c/w selected laminate finishing			
	5.4	To construct and supply rubber solid wood meeting table	1 NO		
		w/height adjustable function			
		Material: Solid wood table top w/ height adjustable frame	100		
		and cable management			
	5.5	To construct and supply 6mm thickness glass w/ coating	25 FR		
	10000 (1000)	aluminium sliding door			
	5.6	To construct and supply 10mm thickness tempered glass	237 SF		
	partition and the same of the	c/w U channel support			
	5.7	To construct and supply 10mm thickness tempered glass	2 NOS		
	versousseld	swing door with handle			
		AND THE PARTY OF T			

6.	AIR-C				
	6.1	To supply and install new Daikin cassette aircon	2 NO		
		Spec: 2.5Hp (R32 Cassette Aircond			
	i i	Extra New Copper Piping 20ft			
		Included dismantle existing 2 set aircond			
7.	LOOSE FURNITURE AND OTHER ITEMS				
	7.1	To supply bar stool w/ 360 degree swivel and height	6 NO		
		adjustable(For meeting room)			
	7.2	To supply and install Philip 4k LED smart TV Size: 55"inch	1 NO		
	7.3	To supply and install HDMI Cable and VGA Cable	1 NO		
		(For TV use)			
_	110.1.4	Items: HDMI cable & VGA cable  PTOP & PC			
8.		O HAUT			
	8.1	HP ProDesk 400G7 MT i5-10500 8GB/256GB SSD PC bundle	2 UNIT		
		with Monitor V5E94AA#AB4 HP V194 18.5-inch			
	0.0	Monitor (S/N : 31P05PA#ARE)	7 115117		
	8.2	HP P440G8U51135GJN256NINCN08NNua A/P bundle with	1 UNIT		
	0.0	HP TopLoad Carrying Case (S/N: 2Y7Y3PA#UUG)	1 115117		
	8.3	HP EliteSlice + HP 14" Monitor (RM5000 + RM800)	1 UNIT		
9.	Manp				
	9.1	3 tonne lorry (2 trips)	1 TRIP		
	9.2	6 pax labors (1 week night job on site)	1 L/S		
		Jumlah Keseluruhan:	RM 200,000.00		

4. Tempoh pelaksanaan bagi kerja-kerja pengubahsuaian ini akan mengambil masa selama empat hingga enam (4-6) minggu.

Sekian, terimakasih.

Yang benar,

Global Elite Ventures Sdn Bhd

Mazlan Muhammad Pengarah Urusan